AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE

PAGE OF PAGES 1 5

2. AMENDMENT/MODIFICATION NO. 0001

3. EFFECTIVE DATE 12/30/2011

4. REQUISITION/PURCHASE REQ. NO. MA-PR617-20120229

5. PROJECT NO. *(If applicable)*

6. ISSUED BY CODE 00094

U.S. DOT/ Maritime Administration
Pacific Div. Acquisition Office
MAR 380-4
201 Mission Street Suite 1800
San Francisco CA 94105

7. ADMINISTERED BY *(If other than Item 6)* CODE 00094

U. S. DOT Maritime Administration
Pacific Div. Acquisition Office
MAR 380.4
201 Mission Street Suite 1800
San Francisco CA 94804

8. NAME AND ADDRESS OF CONTRACTOR *(No., street, county, State and ZIP Code)*

Crowley Technical Management, Inc.
Attn: Patricia Murphy
9487 Regency Square Blvd
Jacksonville FL 32225-8126

CODE 263707071 FACILITY CODE

(x) 9A. AMENDMENT OF SOLICITATION NO.

9B. DATED *(SEE ITEM 11)*

x 10A. MODIFICATION OF CONTRACT/ORDER NO. DTMA8C05014 CTM14P2012006

10B. DATED *(SEE ITEM 13)* 10/28/2011

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☐ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended, ☐ is not extended.
Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGEMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)* Net Increase: $207,421.00
70XR161710.2012.93340ISB00.1261000000.25432.61006600.7012613340ISB0

13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

CHECK ONE	
	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation date, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
X	D. OTHER *(Specify type of modification and authority)* 52.232-18 AVAILABILITY OF FUNDS

E. IMPORTANT: Contractor ☐ is not, ☒ is required to sign this document and return 0 copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION *(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

ISABEL REPAIRS CTM-ISB12-1005 A1
FY12 M&R REPAIRS A - CTM-ISB12-1005A: Task Order Amendment A1
The purpose of modification 0001 is to provide partial funding in support of ongoing FY12 M&R Repairs Phase M Maintenance and Repairs requirements as follows:
1) Extend the Delivery Date to: 31 December 2012.
2) SR1107322 - FORWARD MAST MODIFICATION: The intent is to modify the forward mast for safety reasons to change out light bulbs on the running lights. Furnish labor material and equipment to install pad eyes, turnbuckles and three stay wires to the foremast. Install two separate safety wire climbing system transendors with cable sleeves and safety harnesses to mast, on the two separate ladder rungs from the main deck to the top of the mast. Fabricate and install a light foundation and install at the top of the mast with a
Continued ...

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)* Marian Mobley

16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)* Patricia L. Etridge

15B. CONTRACTOR/OFFEROR Marian Mobley *(Signature of person authorized to sign)*

15C. DATE SIGNED 1-3-12

16B. UNITED STATES OF AMERICA Patricia L. Etridge *(Signature of Contracting Officer)*

16C. DATE SIGNED 1/3/2012

NAME OF OFFEROR OR CONTRACTOR
Crowley Technical Management, Inc.

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	primary and secondary set of navigation LED lights mounted on mast. All work shall be to USCG and ABS rules and regulations. 3) SR4365190 - CARGO HOLD FAN VENT SCREEN RENEWAL: The intent is to renew vent screens with Stainless Steel. Contractor is to provide all labor and materials to remove and use as templates wasted cargo hold ventilation intake screens for fan systems and A Deck Fan Enclosures. Fabricate and renew as original new screens and frames. Replacement screens to be 2 mesh, 120 wire stainless mesh. All frames, hinges and securing latches to be stainless steel. Prime and paint all newly installed and disturbed surfaces. All work shall be to USCG and ABS rules and regulations 4) SR4366105 - FLOORING/PLUMBING/HABITABILITY: Provide labor and materials to renew crew quarters deck flooring and passenger room carpet. Contractor is to provide the necessary labor and materials to remove existing damaged floor tile and cove base. Repair underlayment with marine grade underlayment. Install 1/8-inch gauge commercial 12 X 12 inch coin tile using marine grade base adhesive. Caulk all joints along bulk heads and around equipment with silicone caulking prior to application of rubber cove base. On completion of tile and cove base installation, clean and seal new tile. 5) SR4366108 - MAIN STEAM STOPS MAIN BOILER/BULKHEAD STOP REPAIRS: Contractor is to provide all labor and materials to complete the following valve repairs. All work shall conform to USCG and ABS rules and regulations. 1. Contractor is to open and inspect, lap in and blue for proper seat starboard and port boiler main boiler steam stop valves. Rockwell Edwards, 8-inch, 1500 psi superheated steam. All gaskets shall be replaced, recoat silver ring bonnet seal. Valves shall be repacked with proper steam packing. All work shall be to USCG and ABS rules and regulations. 6) SR4366116 - MAIN THROTTLE HYDRAULIC PUMP REBUILD: The intent is to rebuild throttle pump and return to factory specifications contractor is to provide all labor and materials to rebuild main throttle hydraulic pump. The pump shall be rebuilt to the manufactures specifications. all seals and bearings shall be replaced as per manufactures specifications Continued ...				

NAME OF OFFEROR OR CONTRACTOR
Crowley Technical Management, Inc.

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	Contractor shall supply a condition found report all work shall be to USCG and ABS Rules and Regulations 7) SR4366599 - AIR CONDITIONING COMPRESSOR #1 & #2 REBUILD: The intent is to rebuild the #1 & #2 air conditioning compressors to bring them to like new condition. Contractor is to supply all labor and parts to open and inspect the #1 & #2 AC Compressor. Contractor is to change main bearings and inspect crankshaft for wear. Renew valves and check cylinders, pistons, renew rings, shaft seal is to be replaced; all gaskets shall be renewed; all filters and dryers are to be changed. Sump heaters and oil cooler is to be checked. Check and set lube oil, high head and low suction cutouts and to replace if necessary. New oil shall be added and unit tested. Evacuate system and check TXV valves and shutoff valves; repack if necessary. Check for leaks including the evaporator sections. The system is to be re-charged and tested. All work shall be to USCG and ABS Rules and Regulations. 8) SR4366600 - BOILER FEED WATER REGULATOR REBUILD: The intent is to rebuild both port and starboard boiler feed water regulators and actuators to bring back to like new condition. Contractor is to furnish labor and materials to rebuild both port and starboard boiler feed water regulators. Contractor shall remove boiler feed water regulators to open and inspect seat, plug and replace as needed. All gaskets shall be replaced; air actuators shall be inspected and rebuilt. All work shall be to USCG and ABS Rules And Regulations 9) SR4366964 - BALLAST VALVE AND ACTUATOR, RENEWAL: The intent is to renew #1 ballast tank common valve and actuator and indicator for open and closed lights. Contractor shall provide all labor and materials to remove defective #1 Deep tank ballast valve located in #2 Deep tank; furnish and install new 12-inch bronze butterfly valve with monel disc and shaft, BUNA seat with Stainless steel, return spring, pneumatic opened actuator sized for 80 psi air supply. Contractor is to remove old valve, rig from place and install new valve and actuator, replace all hardware with stainless steel. Modify air supply piping to the new actuator and position indicator cable. Crew will electrically hook up indicator to prove proper operation to the chief engineer. Continued ...				

NAME OF OFFEROR OR CONTRACTOR
Crowley Technical Management, Inc.

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	10) SR4366967 - FUEL OIL HEATER REGULATOR REBUILD: The intent is to rebuild the fuel oil steam regulating valve to bring back to like new condition. Contractor is to provide all labor and materials to remove fuel oil heater steam regulator. Steam regulator shall be rebuilt and tested. Contractor shall rebuild steam regulator as per manufactures specifications and recommendations using new gaskets, seats, springs as needed. Contractor will re-install steam regulator, as original. All work shall comply with ABS and USCG Rules and Regulations. 11) SR4366973 - CARGO DOOR DOGGING CYLINDER AND WEDGE REBUILD: The intent is to rebuild dogging cylinders and replace dogging wedges as needed and hoses back to factory specifications. Contractor is to provide all labor and materials to rebuild all dogging cylinders and replace all hydraulic hoses on cargo doors #2, #3, C Deck. Hydraulic hoses shall be the same size and pressure rating as original. Contractor is to adjust dogs to the door. A chalk test shall be preformed to ensure water tight condition. All work shall be to USCG and ABS Rules and Regulations. Terms and Conditions of the original Task Order are applicable. APPROVED BASELINE BUSINESS PLAN BUDGET: $339,099 Total Amount changed from $63,729.00 to $271,150.00 Obligated Amount for this modification: $207,421.00 CHANGES FOR ACCOUNTING CODE: 70XR161710.2012.93340ISB00.1261000000.25432.61006600.7012613340ISB0 Amount changed from $63,729.00 to $271,150.00 Delivery: 12/31/2012 Delivery Location Code: 00094-ISABEL Cape Isabel Crowley Technical Mgt COTR: AL LIPSKI 2980 Nimitz Road, Pier T-15 Long Beach CA 90802-1048 Payment: MARAD A/P INVOICES 6500 SOUTH MACARTHUR BLVD OKLAHOMA CITY OK 73169 FOB: Destination Continued ...				

NAME OF OFFEROR OR CONTRACTOR
Crowley Technical Management, Inc.

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	Period of Performance: 10/28/2011 to 12/31/2012				