



U S Department of Transportation
Maritime Administration

2. ORDER/CONTRACT NO.
DTMA8C11027 / IAS27P2012005/0002

3. REQUISITION NO.
MA-PR617-20128003

4. PROCURING OFFICE CONTROL NO.

5. QUOTATION REF/OTHER AGENCY CONTRACT NO.

SUPPLY, EQUIPMENT OR SERVICE ORDER/CONTRACT

1. THE NUMBER SHOWN IN BLOCK 2 MUST APPEAR ON ALL SHIPMENTS AND/OR DOCUMENTS RELATING TO THIS ORDER/CONTRACT

6. ISSUED TO
INTER AMERICAN SHIPPING, CORP.
302 HARPER DRIVE SUITE 200
MORRESTOWN, NJ 08057

7. DESTINATION
S INTER AMERICAN SHIPPING, CORP.
H PIER 50
I SAN FRANCISCO, CA 94107-9991
P

T
O

8. DISCOUNT TERMS
N/A

9. DELIVERY F.O.B.
BLOCK 7

10. GOVT B/L NO.
N/A

11. DELIVERY DATE
12/31/2012

12. COTR NAME
TIM COGAN

ADDRESS
201 MISSION STREET SUITE 1800
SAN FRANCISCO, CA 94105

PHONE NO
415-744-2592

13. ITEM NO.	14. DESCRIPTION OF ITEMS OR SERVICES	15. QUANTITY	16. UNIT	17. ESTIMATED TOTAL COST	18. ACTUAL	
					UNIT PRICE	TOTAL COST
	PACIFIC TRACKER IMPROVE / REPLACE IAS-PTK12-1007 A2 The period of performance end date is restored to its original PR request 12/31/12. Increase funding by \$1,010,603.00. The task order total is increased from \$450,000 by \$1,010,603.00 to \$1,460,603.00. This is incrementally funded at \$1,460,603.00. Total value of this Task Order will be \$1,923,425.00. Increase scope of work - SEE ATTACHED SOW. ACCOUNT: 7012171052.2012.81211PZPAT.1211000000.25432.61006600.701211PZPAT000			1,010,603.00		


This is a PERMANENT OBLIGATING document PRISM IS UNAVAILABLE

19. SEND INVOICES IN DUPLICATE TO:
MARAD A/P INVOICES
PO BOX 25710
OKLAHOMA CITY, OK 73125

20. CONTRACTING OFFICER

DATE 2/24/2012

21. REQUISITIONER SIGNATURE
Digitally signed by KEVIN D DWYER
Date: 2012.02.17 10:39:23 -08'00'

22. APPROVING OFFICER SIGNATURE

DATE 2/17/2012

23. FUNDS AVAILABLE -COMMITMENT NO.:
FUND CONTROL OFFICER
Susan Marie Wong
Digitally signed by Susan Marie Wong
DN: cn=Susan Marie Wong, o=DOT, ou=MARAD, email=susan.wong@dot.gov, c=US
Date: 2012.02.23 14:50:43 -0800'

28. QUANTITIES SHOWN IN COLUMN 15 ABOVE HAVE BEEN RECEIVED AND ACCEPTED
 DISCREPANCIES NOTED ON ATTACHED DOCUMENT
SIGNATURE OF RECEIVING OFFICER _____ DATE _____

24. ACCOUNTING DATA
APPROPRIATION -
DIRECT (1) / REIMB. (9) -
FISCAL YEAR -
ALLOTMENT CODE -
COST CENTER -
PROGRAM ELEMENT -
OBJECT CLASS -
REIMB. AGMT. NO. -

25. ACCOUNT-ABLE PROPERTY

26. FIXED ASSET

27. NOT AVAILABLE BUREAU STOCK/ EXCESS

29. PROPERTY CONTROL NO.
ASSET CLASS

MA-PR617-20128003

PACIFIC TRACKER IAS-PCL12-1007A2 IMPROVEMENTS/UPGRADES A2

Increase scope of work as follows (ADD 5 S/R's PER BELOW):

-SR1206807 Bridge Watch Alarm System; Provide and Install

Provide the services of a qualified electronics technician to procure and install an approved Bridge Navigational Watch Alarm System as per the new IMO regulations.

-SR4040258 Phones and Network Stations; Provide

The intent of this work item is to add telephones to existing system and to include LAN access at crew mess and officers lounge.

-SR1206006 Gyros/Steering stands/Repeaters; Renew

Provide labor and material to upgrade the gyros, steering stand and repeaters. Remove existing Sperry gyro compass equipment and renew two main gyros. Renew steering stands and all repeaters. The new gyro system shall be integrated with: 3cm and 10cm radars, ECDIS, S-VDR and AIS.

-SR1206605 OWS; Renew

Provide labor, equipment and materials to replace the vessel's OWS with a new modern unit.

-SR1206612 Mission Chill Water Control Package; Provide and Install

The intent of this work item is to carry out modifications to the Mission Chiller Controls System and to integrate the control system with the Engine Room Console.

-SR1206706 Lifeboat battery charging system; Renew

The intent of this work item is renew the port and starboard lifeboat charging systems with updated system that is part supportive.

-SR1206786 Handrails for Access to False Stack and Mast; Provide and Install

Install a hand railing system on the false stack adjacent in way of the vertical ladder located on the port forward side of the stack. The railings to be installed in a manner to negotiate safe access to the mast and inside of the false stack area.

-SR4040145 Hatch Cover Steps; Provide and Install

Install permanent steel access ladders to the cargo hold hatch covers where there are now wooden ladders.

-SR1206788 Automatic Bilge Pump System; Provide and Install

Install two (2) new sump pumps to the lower engine room drain wells P/S. Tie the new pump discharge piping to the existing pipe line located forward in the lower machinery space. Provide (1) spare pump for ships spares.

-SR4040250 Platform Extension, Stbd Boat Deck; Provide and Install

Install a deck extension to the after outboard section of the boat deck. The new deck platform will enable the reach of the stores crane to the boat deck level.

-SR4040251 Removeable Grating, Hatch Covers; Provide and Install

The intent of this work item is to fabricate and install removable gratings to provide safe access to forward cranes and between hatch covers at #2 and #3 hatches.

-SR4040238 Fresh Water Line; Provide

The intent of this work item is to provide and install a fresh water wash down line to the Fore Deck, TTS Shelters, Aft Port Boat Deck and Port and Starboard Bridge Wings.

-SR1206660 FW pump motor controllers; Renew

The intent of this work item is replace the existing upper and lower fresh water pump motor controllers that are no longer part supportive with new PLC type motor controllers.

****ADD****SR1206576 Engine room lighting; Renew

The intent of this work item renew existing lighting with more efficient fixtures throughout the engine room and machinery spaces.

****ADD****SR1206461 Anchor wash down system; Provide

Install an anchor wash down system using stainless steel piping. Supply to be accomplished by tapping into the existing fire main water supply at the chain locker educator.

****ADD****SR4040195 Bridge Heated Windows; Provide and install

Provide and install a total of five (5) heated windows in the wheelhouse to allow for de-icing during in climate weather.

****ADD****SR4040252 Fire Doors, magnetic release; Provide and Install

Procure and install a magnetic release system for interior house ladder way Fire Doors with control from bridge and EGL one. Renew five interior ladderway doors (Frame 134) on maindeck, upper deck, cabin decks with approved ABS/USCG marine fire doors.

****ADD****SR4040196 Fast Rescue Boat and Davit System; Provide and install

The intent of this work item is to procure, install and test a new certified USCG approved Fast Rescue Boat and davit system on the Port side of vessel IAW SOLAS. Provide Naval architect drawings, certificates and feasibility study. Installation to be reviewed and approved by ABS.